

# **5214 HALE MANUFACTURING DELTA TOILET AND CUBICLE PARTITIONS**

## **1. GENERAL**

### **Requirements**

#### **1.5 QUALIFICATIONS**

Workers to be experienced, competent and familiar with the materials and techniques specified. Installation to be carried out by workers authorised by the screen manufacturer. Delta cubicles are MDF Core only, and not suitable for shower areas.

#### **1.6 WARRANTY**

Warranty this work under normal environmental and use conditions against failure of materials and execution

Warranty period: 2 years

Refer to PRELIMINARIES and GENERAL section for the required form of warranty agreement and details of when completed warranty must be submitted.

## **2. PRODUCTS**

### **Materials**

#### **2.1 PARTITIONING SYSTEM**

Proprietary partitioning system.

##### **Hale Delta System**

Supplier: Hale Manufacturing

Phone: Auckland (09) 573 5999

Phone: Wellington (04) 568 7035

#### **2.2 CHANNELS, RAILS AND BRACKETS**

Extruded aluminium alloy 6063 with powdercoated finish.

#### **2.4 PANELS - MDF**

30/18mm MDF with laminate fully glued both sides.

Door and fascia panels with post-formed radiused edges.

#### **2.5 DOORS**

To match the rigid panels.

## **Components**

### **2.6 HINGES**

To match the aluminium section in size, 3 hinges per door.

Type: Hold open bomber.

Finish: Satin chrome.

### **2.7 PEDESTALS**

Metal standard with flanged top to screw fix to panel.

Concrete Floor Type: Stainless steel with Dynabolt into floor. No surface fixing visible.

Wooden Floor Type: Stainless steel with flange screw fixed to floor.

## **3.0 EXECUTION**

### **Conditions**

#### **3.1 HANDLE AND STORE**

Handle and store tracks, studs, panels and accessories to avoid damage. Keep dry in transit, store clear of and on a level floor and cover for protection.

#### **3.2 SUBSTRATE**

Ensure substrate plumb, level and in true alignment.

#### **3.3 PROTECT**

Protect adjoining areas, surfaces and finish from damage.

### **Application**

#### **3.4 INSTALL SCREENS**

Carry out the fixing, erection and fitting to finish rigid, plumb, true to line and face and square, to the screen manufacturer's requirements.

#### **3.5 INSTALL COMPONENTS**

Hang doors and fit hardware to the screen manufacturer's requirements.

### **Completion**

#### **3.6 REPLACE**

Replace damaged or marked elements

### **3.7 LEAVE**

Leave work with parts fully and freely working and to the standard required by following procedures.

### **3.8 REMOVE**

Remove debris, unused materials and elements from the site.

## **4. SCHEDULES**

### **4.1 PARTITIONING SYSTEM**

**Manufacturer: Hale Manufacturing Ltd**

**Brand: Delta**

### **4.2 CHANNELS, RAILS AND BRACKETS**

Colour: Standard Duralloy powdercoat to be advised.

### **4.4 PANELS, MDF core only. Not to be used in direct shower areas.**

Laminate: T.B.A. (Price based on Formica/WilsonArt)

Finish: T.B.A. Postforming grade onlly.

### **4.5 HARDWARE**

Indicator bolt and keeper:Hale, SCP finish - Delta Suite. Concealed fixing.

Hat and coat hooks: Hale, SCP finish - Delta Suite. Concealed fixing